



APPENDIX C –  
UPDATED PROJECT DESCRIPTION



## C.1 Updated description of the modified project

TableC.1 In accordance with the Draft EIA guidelines, a consolidated description of the modified project must be included as an appendix to the Modification Report.

TableC.1 Updated project description

| Element                                | Project description   |
|--|---|
| <b>Quarry life</b>                     | 31 December 2024  |
| <b>Production rate</b>                 | 300,000 tpa   |
| <b>Maximum extraction depth</b>        | 30 m  |
| <b>Quarry footprint</b>                | As per Appendix A of consent.   |
| <b>Hours of operation</b>              | Operations 7 am to 6 pm Monday to Friday.<br>No haulage vehicles to enter the site between 6 pm and 7 am Monday to Friday.<br>Maintenance 7 am and 1 pm Saturday                      |
| <b>Stockpiles</b>                      | Western stockpiling area 11,000 m <sup>2</sup> and stockpiling within approved extraction area.<br>Maximum volume of clay and shale stockpiled on site up to 250,000 m <sup>3</sup> . |
| <b>Site access road</b>                | Access via existing property access on Adams Road.  |
| <b>Vehicle movements</b>               | Up to 100 product movements.  |
| <b>Noise limit</b>                     | A western and an eastern noise bund as shown in Appendix A of the consent.<br>The northern noise bund will be removed during construction of the ARRC.                                |
| <b>Blasting</b>                        | No blasting.  |
| <b>Waste</b>                           | No disposal, storage, processing of waste unless permitted by an EPL.   |
| <b>Surface water management system</b> | As described in Section 2.5 of this report.   |